


17-15-1W⁸



Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

March 17, 1986

COMPANY: EXCALIBUR PRODUCTION CO., INC.
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: GILLMORE #B-1
LOCATION: 330' from East & 460' from South
SE/4 Section 17-15S-1W
Saline County, Kansas
COMMENCED: March 10, 1986
COMPLETED: March 14, 1986
ELEVATION:

MAR 24 1986
C. E. Plouffe

0	to	460	Lime
460	to	915	Lime & Shale
915	to	2110	Shale & Lime
2110	to	2722	Lime
		2722	T. D.


Cut 12 $\frac{1}{4}$ " hole to 200.78' and run 202.78' of 8 5/8" surface casing, cemented with 130 sacks of cement at 200.78'. Plug down at 10:30 P. M., March 10, 1986. Filled hole to 250' with mud & spot 50 sacks of cement. Filled hole with mud & spot 25 sacks of cement at 60', 10 sacks of cement in rathole. Plugging completed at 5:30 P. M. by State Plugger, Phil Whorley, State Plugger, Salina Office.

TOPS:

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true copy of log on your Gillmore B#1, located on the 330' from East & 460' from South of SE/4 Section 17-15S-1W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.


P. E. PLOUFFE, PRESIDENT

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 17th day of March, 1986.

