


JAN 3 1970



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS

November 10, 1969

30-15-1W


30-15-1W

CNE SE

COMPANY: DALE REESE OIL COMPANY
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: HESS #1
LOCATION: C-NE/4 SE/4 Sec. 30-15-1W
Saline County, Kansas
COMMENCED: November 5, 1969
COMPLETED: November 10, 1969
ELEVATION: 1305 K. B.

oil

0	to	125	Shale & Lime
125	to	885	Lime
885	to	1530	Shale
1530	to	1875	Shale & Lime
1875	to	1982	Lime & Shale
1982	to	2046	Brown Lime
2046	to	2190	Lansing
2190	to	2670	Lime
2670	to	2707	Mississippi
		2707	T. D.



Cut 12 1/4 in. hole to 125 ft. and run 129 ft. of 8 5/8 in. surface pipe, cemented with 90 sacks of cement at 125 ft., plug down at 6:00 P. M., November 5, 1969. Cut 7 7/8 in. hole to 2707 ft. and run 2710 ft. of 5 1/2 in. pipe, cemented with 35 sacks 7 ft. off bottom at 2700 ft., plug down at 2:30 A. M., November 10, 1969.

TOPS: BROWN LIME - 1982' LANSING - 2046' MISSISSIPPI - 2670

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Hess #1, located on the C-NE/4 SE/4 Sec. 30-15-1W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.


H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 10 day of November, 1969.