

GEOLOGICAL SOCIETY  
508 East Murdock  
Wichita, Kansas

SEP 19 1970



# Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

February 25, 1970

30-15-140  
C-E/2 E/2 E/2

COMPANY: DALE REESE OIL COMPANY

CONTRACTOR: BLACKSTONE DRILLING, INC.

FARM: HESS #2

LOCATION: C-E/2 E/2 E/2, Sec. 30-15-1W,  
Saline County, Kansas

COMMENCED: February 16, 1970

COMPLETED: February 24, 1970

ELEVATION: 1303 K. B. *1303' KB*

*10 BOPD + 5 g with  
miss*

0	to	635	Line
635	to	940	Line & Shale
940	to	1710	Shale & Line
1710	to	1830	Line
1830	to	2043	Shale & Line
2043	to	2090	Kansas City Line
2090	to	2525	Line
2525	to	2670	Shale & Line
2670	to	2722	Mississippi
		2722	T. D.



Cut 12 1/4 in. hole to 120 ft. and run 122 ft. of 8 5/8 in. surface pipe, cemented with 10 sacks of cement at 120 ft., plug down at 12:00 A. M., February 16, 1970. Cut 7 7/8 in. ole to 2722 ft. and run 2715 ft. of 5 1/2 in. pipe, cemented with 40 sacks of cement - ft. off bottom at 2718 ft. Plug down at 3:30 A. M., February 24, 1970.

TOPS: Kansas City - 2043' *2043* Mississippi - 2670'

Measurements taken from K. B.

### CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Hess #2, located on the C-E/2 E/2 E/2, Sec. 30-15-1W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.

*H. J. Plouffe*  
H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 25 day of February, 1970.

*Johnnie L. ...*