

15-169-20056

State Geological Survey

WICHITA BRANCH

KANSAS DRILLERS LOG

S. 31 T. 15 R. 1 ^{EX}W

Loc. SW NW NE

County Saline

API No. 15 _____
County _____ Number _____

Operator
George R. Hess

Address
Box 89, McPherson, Ks. 67460


Well No. #6 Lease Name Hess

Footage Location
660 feet from (N) line 330 feet from (W) line

Principal Contractor Blackstone Drilling, Inc. Geologist George R. Hess

Spud Date 6-1-72 Total Depth 2705 P.B.T.D.

Date Completed 6-5-72 Oil Purchaser NCRA



Locate well correctly

Elev.: Gr. _____

DF _____ KB 1313

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	32	132	Portland	100	
Oil String	7 7/8	5 1/2	14 1/2	2700	Portland	35	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		
Size	Setting depth	Packer set at
2"	2700	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal. 15%	2700-05

INITIAL PRODUCTION


Date of first production June 18, 1972 Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS
Oil 8 bbls. Gas 0 MCF Water 50 bbls. Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Producing interval(s) 2700-05

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

SEP 8 1972



Blackstone Drilling, Inc.


Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS

June 6, 1972

31-15-1W
SW NW NE

API # 15-169-20, 056



COMPANY:

GEORGE R. HESS

CONTRACTOR:

BLACKSTONE DRILLING, INC.

FARM:

HESS #6

LOCATION:

SW NW NE, Sec. 31-15-1W,
Saline County, Kansas

COMMENCED:

May 31, 1972

COMPLETED:

June 5, 1972

ELEVATION:

1313 K. B.

IP: 6 BOPD & 50 BWP
MISS

0	to	130	Shale & Shell
130	to	375	Lime & Shale
375	to	1635	Shale & Lime
1635	to	1815	Lime & Shale
1815	to	2060	Shale & Lime
2060	to	2385	Lime
2385	to	2575	Lime & Shale
2575	to	2689	Lime
2689	to	2705	Mississippi
		2705	T. D.

Cut 12 1/4 inch hole to 130 ft. and run 132 ft. of 8 5/8 inch pipe, cemented with 100 sacks of cement at 130 ft., plug down at 11:00 A. M., June 1, 1972. Cut 7 7/8 inch hole to 2705 ft. Run 2737 ft. of 5 1/2 inch pipe, cemented with 35 sacks of cement 5 ft. off bottom. Plug down at 12:00, June 5, 1972.

TOPS: KANSAS CITY - 2070' MISSISSIPPI - 2689'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your HESS #6, located on the SW NW NE, Sec. 31-15-1W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.

Blackstone Drilling, Inc.
by H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 6th day of June, 1972.