


KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCHAPI No. 15 — 169 — 20,063
County Number

S. 31 T. 15 R. 1 E W

Loc. NE NW NE

County Saline

640 Acres
N

Elev.: Gr. _____

DF _____ KB _____

Operator

George R. Hess

Address 505 N. Charles McPherson, Kansas

Well No.

#7

Lease Name

Hess

Footage Location

330 feet from (N) line 990 feet from (W) line

Principal Contractor

Black Stone Ry Co

Geologist

George Hess

Spud Date

March 25 1924

Total Depth

2718

P.B.T.D.

None

Date Completed

March 30 1924

Oil Purchaser

None

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	28	142	Portland	90	
Oil string	7 7/8	4 1/2	16	2714	Portland	35	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Temporary No Completion. Lost tools in Hole	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

April 2, 1974

31-15-1W

COMPANY: GEORGE R. NESS
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: NESS #7
LOCATION: NE NW NE, Sec. 31-15-1W,
Saline County, Kansas
COMMENCED: March 28, 1974
COMPLETED: March 30, 1974
ELEVATION:

0	to	140	Shale & Lime
140	to	785	Lime
785	to	1405	Shale & Lime
1405	to	1680	Lime
1680	to	1885	Lime & Shale
1885	to	2064	Shale & Lime
2064	to	2150	Lansing
2150	to	2410	Lime
2410	to	2565	Lime & Shale
2565	to	2691	Shale
2691	to	2718	Mississippi
		2718	T. D.

Cut 12 1/4 inch hole and run 142 ft. 8 5/8 inch casing, cemented with 90 sacks of cement at 140 ft., plug down at 6:00 p. m., March 28, 1974. Cut 7 7/8 inch hole to 2718 ft. and run 2728 ft. of used 4 1/2 inch casing, cemented 4 ft. off bottom at 2718 ft., cemented with 25 sacks of cement. Plug down at 6:00 a. m., March 30, 1974.

TOPS: Mississippi - 2691'

Measurements taken from K. B.

CERTIFICATE

I, Charles D. Johnson, Secretary-Treasurer of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Ness #7, located on the NE NW NE, Section 31-15-1W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.



Charles D. Johnson, Secretary-Treasurer

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas
2nd day of April, 1974.

