



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

February 11, 1976

COMPANY: DALE REESE OIL COMPANY
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: MORTIMER #1
LOCATION: C SW/4 NW/4 SW/4, Section 31-15-1W,
Saline County, Kansas
COMMENCED: February 4, 1976
COMPLETED: February 10, 1976
ELEVATION: 1310 K. B.

0	to	40	Lime
40	to	118	Blue Shale
118	to	345	Lime & Shale
345	to	710	Shale
710	to	1030	Shale & Lime
1030	to	1440	Lime & Shale
1440	to	1790	Shale
1790	to	2055	Lime & Shale
2055	to	2275	Shale & Lime
2275	to	2716	Lime
2716	to	2740	Mississippi
		2740	T. D.

Cut 12 $\frac{1}{4}$ " hole to 118' and run 120' of 8 5/8" surface casing, cemented with 100 sacks of cement at 118'. Plug down at 2:30 P. M., February 4, 1976. Hole dry and abandoned. Set plug at 140' with 25 sacks of cement. Set second plug at 40' with 10 sacks of cement with 2 sacks in rathole. Plugging completed at 7:00 P. M., February 10, 1976. Plugging completed by Hugh Scott, State Plugger, McPherson, Kansas.

TOPS: MISSISSIPPI - 2716'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Mortimer #1, located C SW/4 NW/4 SW/4, Section 31-15-1W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.


P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 11th day of February, 1976.


Johnnie L. Schmidt - Notary Public

