

APR 25 1970
Miller "B" #5

33-15-1W
SW NW NW
33-15-1W



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

March 26, 1970

COMPANY: CAL JONES
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: MILLER B #5
LOCATION: SW/4 NW/4 NW/4, Sec. 33-15-1W,
Saline County, Kansas
COMMENCED: March 21, 1970
COMPLETED: March 25, 1970
ELEVATION: 1285 K. B.

30 BOPD
min

0	to	130	Line
130	to	295	Line & Shale
295	to	580	Line
580	to	835	Line & Shale
835	to	1973	Shale & Line
1973	to	2045	Kansas City
2045	to	2555	Line
2555	to	2610	Shale & Line
2610	to	2615	Mississippi
		2615	T. D.

Cut 12 1/4 in. hole to 130 ft. and run 133 ft. of 8 5/8 in. surface pipe, cemented with 100 sacks at 130 ft., plug down at 12:30 P. M., March 21, 1970. Cut 7 7/8 in. hole to 2615 and run 2638 ft. of 5 1/2 in. pipe, cemented with 30 sacks 5 ft. off bottom at 2610 ft., plug down at 8:45 A. M., March 25, 1970.

TOPS: BROWN LIME - 1912' KANSAS CITY - 1973' MISSISSIPPI - 2610'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Miller B #5, located on the SW/4 NW/4 NW/4, Sec. 33-15-1W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 26 day of March, 1970.