


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HENDERSON OIL CO.
Farm- Zvolanek "C" No. 1

SEC. 29 T. 15 R. 10W
C SE/4

Total Depth. 3360'
Comm. 11-12-59 Comp. 11-20-59
Shot or Treated.
Contractor. Birmingham-Bartlett Drlg.
Issued. 1-23-60

County Ellsworth
KANSAS



CASING:

8 5/8" 357' cem w/225 sx.

Elevation. 1810' DF

Production. Dry

Figures Indicate Bottom of Formations.

clay & post rock	60
shale & shells	575
red bed	645
Anhydrite	675
shale	692
shale & red bed	870
shale & shells	1450
broken lime	1550
lime & shale	1825
shale	2015
shale & shells	2200
shale & lime	2560
lime	2605
lime & shale	2760
lime	3230
lime & shale	3337
sand	3342
shale & sand	3352
Arbuckle	3360 RTD
Total Depth	

TOPS:

Anhydrite (scout)	645
Topeka	2604
Heebner	2854
Toronto	2874
Brown Lime	2954
Lansing	2967
Base Kansas City	3253
Marmaton Lime	3274
Simpson Sand	3330
Arbuckle Dolomite	3353

DST #1 3328-3337', op 1 hr., weak blow for 10 min & quit. Rec. 30' of mud, IFP 45#, FFP 45#, BHP 601#. At start of test packer leaked for a few minutes & this is probably where most of the 30' of mud came from.