


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. SHIELDS OIL PRODUCERS  
Farm- Nejd1 No. 1

SEC. 31 T. 15 R. 10W  
NE SE NE

Total Depth. 3246  
Comm. 7-3-55 Comp. 7-14-55  
Shot or Treated. 500 gal. - Squeeze - 500 gal.  
Contractor. Shields Drilling Co., Inc.  
Issued. 9-10-55

County Ellsworth  
KANSAS



Elevation. 1759 RB

CASING:

8 5/8 370' w/ 200 sx cmt.  
5 1/2 3242' w/ 75 sx cmt.

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	35
shale	70
sand	95
shale	160
sand	250
shale	420
red bed	810
shale & shells	1045
shale	1150
shale, shells & salt	1275
shale & lime streaks	1330
lime & shale	1620
lime	1695
lime & shale	1890
shale	2260
shale & lime streaks	2370
shale	2496
lime & shale	2580
lime	2660
lime & shale	2784
lime	3237
conglomerate	3241
Arbuckle	3246
Total Depth	RTD 3245'

SCOUT TOPS:

Toronto	2824
Conglomerate	2840
Lansing	2901
Arbuckle	3240

DST #1: 3242-45, open 2 hrs. wk. int.  
blow, rec. 40' oil, 20' OCM, IFP 0 #  
FFP 28#, BHP 482#/20 min.