

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - CITIES SERVICE OIL COMPANY
Farm - Vacek No. 2

SEC. 32 T. 15 R. 10W
SW NE SW
990' S, 990' W of center

Total Depth. 3293
Comm. 2-28-50 Comp. 3-14-50
Shot or Treated. none
Contractor. Lohmann-Johnson Drlg.
Issued. 5-27-50

County. Ellsworth
KANSAS



CASING:
8 5/8" 426' cem w/225 sx.
5 1/2" 3287' cem w/125 sx.

Elevation. _____

Production. Pumped 123 oil, no wtr

Figures indicate Bottom of Formations.

surface soil, shale	41
shale	345
sand, shale	380
shale, shells	720
shale, salt, shells	1270
shale, shells	1350
lime, shale	1380
lime	1468
lime, shale	1740
shale, shells	2155
shale	2295
shale, shells	2540
lime, shale	2775
lime	2890
lime, shale	2934
lime	2966
lime, shale	3088
lime	3283
3283 RTD = 3287 SLM	
lime	3293
Total depth	

Tops: Corr.
Lansing 2949
Simpson 3271
Eros. Arbuckle 3281
Arbuckle 3285
Penetration 8'

Fillup: 950' oil in 1 3/4 hrs.
1200' oil in 2 3/4 hrs.
1550' oil in 3 3/4 hrs.
1800' oil in 4 3/4 hrs.
2000' oil in 5 3/4 hrs.
2100' oil in 6 3/4 hrs.