


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL CO.
Farm- Vacek No. 6

SEC. 32 T. 15 R. 10W
C EL SE SW
660' N 330' W of S $\frac{1}{4}$ cor.

Total Depth. 3327'
Comm. 4-29-57 Comp. 5-10-57
Shot or Treated.
Contractor. Braden Drlg. Co.
Issued. 8-24-57

County Ellsworth
KANSAS



Elevation. 1826'

Production. 31 BO/6 wtr. 24 hrs.

CASING:

8 5/8" 432' w/250 sx cem.
5 1/2" 3320' w/100 sx cem.

Figures indicate Bottom of Formations.

shale-shells	170
lime-shale	605
shale-shells	1380
Anhydrite	1415
lime-shale	1560
lime	1850
lime-shale	1950
shale-shells	2405
lime	3293
lime-chert-shale	3311
lime	3322
3322 Rotary T.D. = 3321 S.L.M.	
lime	3327
Total Depth	

TOPS:

Corr. Heebner	2862
" Dodge	2882
" Douglas	2902
" Lansing	2962
W Cherty conglomerate	
	3289
" Eros. Arbuckle	3307
" Arbuckle	3318
Pen.	9

368' oil 14 hrs. @ 3321'.

5-24-57 Acidized 250 gals. @ 3321
5-31-57 Deepened 3321-27.
6-5-57 Acidized 500 gals.
6-12-57 " 1500 gals.