


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HENDERSON OIL CO.
Farm-Zvolanek No. 1

SEC. 32 T. 15 R. 10W
NE NE NE

Total Depth. 3375
Comm. 6-14-55 Comp. 6-23-55
Shot or Treated.
Contractor. Garvey Drilling Co.
Issued. 8-20-55

County Ellsworth
KANSAS



CASING:
8 5/8 @ 360' w/ 230 sx cmt.

Elevation. 1781 RB

Production. Dry

Figures indicate Bottom of Formations.

surface clay	60
shale, rock & sand	150
shale	193
sand	225
shale & shells	460
red bed	525
sand & shale	610
red bed & shale	860
shale & shells	1120
shale, shells & sand	1290
shale & lime	1325
shale & shells	1410
lime & shale	2285
shale	2350
lime & shale	2942
lime	3222
shale & lime	3295
conglomerate	3338
Arbuckle	3375
Total Depth	
TOPS:	
Howard	2521
Topeka	2569
Heebner	2826
Toronto	2847
Douglas	2856
Brown lime	2928
Lansing	2942
Drum	3089
Base KC	3240
Conglomerate	3275