


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 503 East Murdock, Wichita, Kansas

Company: HARRY D. THOMPSON AND M. F. BEAR
 Farm: Sebasta No. 2

SEC. 33 T. 15 R. 10W
 SE SE SW SE

Total Depth. 3275'
 Comm. 2-28-56 Comp. 3-9-56
 Shot or Treated.
 Contractor. Lewis Drlg. Co.
 Issued. 5-12-56

County Ellsworth
 KANSAS



CASING:
 8 5/8" 329'
 5 1/2" 3271'

Elevation. 1717' KB

Production. 129 BOPD

Figures indicate Bottom of Formations.

surface clay	60
sand and shale	329
shale & red beds	600
shale	1130
shale and lime	1555
lime	1754
lime and shale	3017
lime	3096
lime and shale	3224
lime	3275
Total Depth	

Tops:	
Heebner	2758
Douglas	2787
Brown Lime	2855
Lansing	2874
Plattsburg	2900
Wyandotte	2922
Lane	2960
Munice Creek	3012
Drum	3023
Westerville	3037
Dennis	3059
Swope	3095
Hertha	3157
Base Kansas City	3166
Marmaton	3184
Arbuckle	3270

DST #1 3271-75', weak blow 1 hr., rec. 1' free
 oil, 860' of very heavy oil cut mud.
 BHP 1010#, IFP 0#, FFP 0#