

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

November 12, 1970

NOV 13 1970

WELL PLUGGING AUTHORITY

Well No.	1
Lease	<u>Henry Macek</u>
Description	C N/2 NE NE 15-15-10W
County	Ellsworth
Total Depth	3280
Plugging Contractor	H-30, Inc.

Glen Rupe & Stan Bell
222 Brown Bldg.,
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,

\$ 32.80

J. Lewis Brock
J. Lewis Brock, Administrator

Billidin

Nov


#135

Mr. Gilbert Toman Box 180 Holyrood, Kansas
is hereby assigned to supervise the plugging of the above
named well.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellsworth

County. Sec. 15 Twp. 15S Rge. 10 (E) (W)

Location as "NE/CNW/SW" or footage from lines 330' S of NL, 550' W of EL NE 1/4

Lease Owner Glen Rupe and Stan Bell

Lease Name Henry Macek

Well No. 1

Office Address 222 Brown Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 7, 1970

Application for plugging filed Verbal Approval Request

Application for plugging approved Verbal Approval

Plugging commenced November 7, 1970

Plugging completed November 7, 1970

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	249'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 3,280 feet (rotary total depth) to 500 feet. Set bottom plug at 500 feet and cemented with 40 sacks of cement. Filled hole with heavy rotary mud to 240 feet. Set plug at 240 feet and cemented with 25 sacks of cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented with 10 sacks of cement, 2 sacks cement in rathole. Well plugging operation accomplished utilizing Sun Oilwell Cementing, Inc. pump truck.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
Address 200 North Main, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Dean Britting, Agent (employee of owner) or (owner or operator) of the above-described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 North Main- Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 11th. day of November, 1970

My commission expires June 30, 1974

Elsie Willison
Notary Public.

11/13/70 copy given
11/27/70 Bell