

TRAPP

Form 113 50M 6-47-41683-D

State Kansas County Russell (MAO)Sec. 10 Twp. 15 Rng. 13w Elev. 1860Company Sohio et alWell No. 6 Name AnschutaLocation SW SE NW($\frac{1}{4}$ mile N Lease #18727, $\frac{1}{4}$ W #47459)

Feet from lines: N. S. E. W.

Spud 9-28-47 Completed 11-19-47T. D. 3528 Casing 5" 3398PB 3040Comp. Perf. 76 $\frac{1}{4}$ 2966-84Pay 2966-84 in DodgeI. P. 56 BOPD $\frac{1}{4}$ 36% wtr.

Choke T. P. C. P.

G. O. R. Grvty.

DATE

REMARKS

11-19-47 Anhy. 818, Dodge 2974, Lans. 3028,
 Cgl. 3315, Row Arb. 334, Arb. 3347,
 Reg. 3520, DST 2970-86, open 40
 min., gd. blw., rec. oil & gas,

DYLE

DATE	REMARKS
	cut mid. TD 3500, Ran Schlum
DATE	3342, DD 3528 RTD, 12 #
	3113-46, 65 GMPH, LWplug
G O B	3139, 12 # 3126-29, 2 1/2 BOPH,
	Plug 3120, 24 # 3106-12
Spoke	500 A, Swb/26 GO + 10 GMPH/8
	2000 A, Swb/1 BO + 1/2 BOPH,
I B	plug 3090, 12 # 3062-69,
	1000 A, Swb/1 BO + 1/2 BOPH/8
Bay	Plug 3040, 76 # 2966-84, 500
	A, B/2 1/2 BOPH + 42% wtr/7
Comb. B	Est. 40 BOPD.
L D	Phy. pet. 56 BOPD + 36% wtr.
2500	COMPLETE
Less from	Plugs: 11 2 E W
(1 1/2 WTR) & 10000 4215 (1 1/2 # 10000)	
Location	24 05 NN
Well No.	Name
Combustion	
Sec	LWB R BGR T3 Elev
2100	Compt
	1949