

19-15-11W
✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- R. P. NIXON
Farm- Herber No. 1

SEC. 19 T. 15 R. 11W
SW NW SE

Total Depth. 3310'
Comm. 4-4-62 Comp. 4-14-62
Shot or Treated.
Contractor. Shields Drilling Co., Inc.
Issued. 10-6-62

County Russell
KANSAS



CASING:
8 5/8" 275' cem w/175 sx.
4 1/2" 3308' cem w/125 sx.

Elevation. 1859' RB

Production. 25 BOPD, NW

Figures Indicate Bottom of Formations.

surface soil, clay post rock	70
shale & sand	275
shale & shells	350
sand	475
shale & shells	700
red bed	735
anhydrite	762
shale & lime	2250
shale	2485
shale & lime	2735
lime	3304
granite wash	3310 RTD
Total Depth	

DST #6 3281-3310' op 1 hr. w/fair blow.
Rec. 500' gas, 180' muddy oil. FBHP 780#.

TOPS:	
Topeka	2609
Heebner	2900
Toronto	2917
Brown Lime	2990
Lansing Kansas City	2998
Granite Wash	3305

DST #1 2919'-2930' op 30 min. Rec. 40'
gas, 20' mud. FBHP 0#.

DST #2 3084-3091' op 1 hr. w/fair blow.
Rec. 165' gas, 2' SO & GCM, 60' mud.
FBHP 730#.

DST #3 2830-2845' op 1 hr. Rec. 30'
muddy water. FBHP 380#.

DST #4 3165-3177' Tool op w/weak blow.
Rec. 15' mud w/specks of oil. FBHP 0#.

DST #5 3188-3200' op 1 hr. w/fair blow.
Rec. 90' water w/trace of oil & gas.
FBHP 480#.