

State Geological Survey  
WICHITA, BRANCH  
CONTRACTOR'S WELL LOG

15-167-20822 ✓  
22-15S-11W

OPERATOR: Wilson Exploration & Development, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: PERTL #2  
 LOCATION: SW NW SE Section 22-15S-11W  
 Russell County, Kansas  
 SPUD DATE: December 18, 1975  
 COMPLETION DATE: December 27, 1975

0	25	Clay, rock
25	80	Rock
80	180	Sand & shale
180	716	Shale
716	738	Anhydrite
738	1145	Shale
1145	1506	Shale & lime
1506	2890	Lime & shale
2890	3344	Lime
	3344	Rotary Total Depth

Drilled 256' of 12¼" hole. Ran 7 jts. 28# 8 5/8" casing, Set @ 254 K.B. Cemented with 140 sx. Quick-Set cement. Cement did Circulate. Plug was down @ 2:00 a.m. December 18, 1975.  
 Ran 83 jts. of 5½" casing. Set @ 3337'. Job complete @ 7:15 p.m. December 27, 1975.

SAMPLE TOPS:

Anhydrite 716  
 B/Anhydrite 738

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the PERTL #2, SW NW SE section 22-15S-11W, Russell County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr  
 Jerry A. Langrehr-Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 8th day of January, 1976.



Sandra Richman  
 Sandra Richman - Notary Public