

32-15-11W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- S & C DRILLING, INC.
Farm- Alvin Borell No. 2
"B"

SEC. 32 T. 15 R. 11W
NW SE NE

Total Depth. 3330'
Comm. 2-25-63 Comp. 3-28-63
Shot or Treated.
Contractor.
Issued. 6-1-63

County Russell
KANSAS



Elevation. 1860' KB

Production. 50 BOPD, NW

Figures Indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE:

- 2844-2859: Limestone chalky w/some gray chert, trace of dark, free oil, spotted staining.
- 3318-3320: Dolomite, fine crystalline, no odor, no free oil, poor porosity w/slight staining.
- 3320-3325: Dolomite, fine to medium crystalline, faint odor, small show of free oil, slight porosity, fair staining.
- 3325-3330: Dolomite, medium to coarse crystalline, good odor, good show of free oil, good inter-crystalline porosity w/fair to excellent staining.

TOPS:	SAMPLE	
Anhydrite		710
Topeka		2652
Heebner		2893
Toronto		2913
Douglas		2924
Brown Lime		2984
Lansing		2993
Shaley Conglomerate		3285
Cherty Conglomerate		3303
Arbuckle		3318
Pay Section		3324

Rotary Total Depth 3330

DST #1 3320-25' op 1 hr., weak blow for 13 mins. Rec. 12' of slightly oil cut mud, no water. ICIP 839#/30 mins.; FCIP

749#/30 mins. Flow pressures, zero.