

32-15-11W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **ROBINOWITZ OIL CO.**
Farm- **Davidson** No. **4**

SEC. **32** T. **15** R. **11W**
 NE SE SE

Total Depth. **3283'**
Comm. **3-20-63** Comp. **3-27-63**
Shot or Treated.
Contractor. **Sholom Drlg. Co., Inc.**
Issued. **7-27-63**

County **Russell**
 KANSAS



CASING:
8 5/8" 289' cem w/175 sx.
5 1/2" 3269' cem w/100 sx.

Elevation. **1819'** **KB**

Production. **100 BOEPD/NO WTR.**

Figures Indicate Bottom of Formations.

clay, rock & shale	100
shale	288
dry Dakota & pyrite & shale	470
shale & sand	480
red bed	674
anhydrite	700
shale & shells	1060
sandy shale & lime streaks	1410
shale & shells w/sandy lime streaks	1600
lime	1890
shale & lime streaks	2035
shale & lime	2305
lime & shale	2475
shale & shells	2590
lime & shale	2730
lime	2777
lime & shale	2885
shale	2945
lime	3040
Kansas City lime & shale	3060
lime	3190
lime & shale	3255
conglomerate	3264
arbuckle	3273 RTD
arbuckle ?	3283
Total Depth	

TOPS:

Anhydrite (Driller)	674
Topeka	2611
Heebner	2853
Toronto	2873
Douglas	2885
Lansing	2944
Base Kansas City	3195
Marmaton	3199
Conglomerate	3242
Simpson	3260
Arbuckle	3264

DST #1 3186-3273' Rec. 70' OCM