

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


32-15-11W

Company- ROBINOWITZ OIL & PETROLEUM OPERATING
Farm- Davidson No. 6

SEC. 32 T. 15 R. 11W
NW NE SE

Total Depth. 3405'
Comm. 5-7-63 Comp. 5-15-63
Shot or Treated.
Contractor. Sholom Drlg,
Issued. 11-30-63

County Russell
KANSAS



CASING:

Elevation. 1826' KB

8 5/8" 285' cem w/ 175 sx
5 1/2" 3354' cem w/100 sx

Production. 25 BOPD

Figures Indicate Bottom of Formations.

post rock & shale	40
shale	277
plug & cement	285
shale & sand	320
sand & streak of Pyrite	370
hard sand & Pyrite	410
shale & sand streaks	485
red bed	682
anhydrite	709
shale & shells	910
shale & shells	1413
lime & shale	2565
lime	2705
lime & shale	2880
lime	3214
lime & shale	3277
lime, shale & chert	3311
Arbuckle	3405
Total Depth	

TOPS: SCOUT

Anhydrite	682- 709
Topeka	2617
Plattsmouth	2800
Heebner	2858
Toronto	2874
Douglas	2890
Lansing	2950
Base Kansas City	3195
Conglomerate	3261
Arbuckle	3311

DST #1 3227-3317 Rec. 700' SOCM, 90'
SOCMW, 150' SOCMW.

DST # 2 3355-61 (Straddle at 3405)
Rec. 2400' S. W.