

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


32-15-11W

ROBINOWITZ OIL COMPANY &
Company- PETROLEUM OPERATING COMPANY
Farm- Davidson "B" No. 1
"Davidson 2"

SEC. 32 T. 15 R. 11W
SE NE SE

Total Depth. 3274'
Comm. 10-18-62 Comp. 10-26-62
Shot or Treated.
Contractor. Sholom Drilling Co., Inc.
Issued. 3-9-63

County Russell
KANSAS



CASING:

8 5/8" 286' cem w/175 sx.
5 1/2" (used) @ 3268' cem w/100 sx.

Elevation. 1818' KB

Production. 25 BOPD

Figures Indicate Bottom of Formations.

clay	20
post rock	65
shale	160
sand	190
shale & clay	240
sand, shale, & clay	267
plug & cement	286
shale & sand	332
hard sand & pyrite	340
sand	370
sand & shale	380
hard sand & pyrite	396
shale & sand	410
pyrite & shale	465
red bed	667
anhydrite	697
shale & shells	1310
lime & shale	2580
lime	2890
shale & lime	2957
lime	3235
lime & shale	3263
shale	3266
arbuckle	3274 RTD
Total Depth	

TOPS:

Anhydrite	667 - 697 (dr)
Topeka	2607
Heebner	2849
Toronto	2871
Douglas	2883
Lansing	2943
Base Kansas City	3191
Conglomerate	3238
Reworked Simpson	3247
Arbuckle	3266

DST #1 2856-2890' Rec. 570' GCWM.

DST #2 3268-3274' Rec. 1550' oil.