

33-15-11W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY SEEGER OIL & GAS CO.

SEC. 33 T. 15 R. 11W
LOC. SW NW NE

FARM Borell

NO. 1

TOTAL DEPTH 3200

COMM. 2-7-51

COMP. 2-28-51


SHOT OR TREATED

CONTRACTOR Sterling Drilling Co. & Gleason Drlg. Co.

ISSUED 3-31-51

COUNTY Russell

KANSAS



CASINO

8 5/8" 287' cem. w/150 sx

5 1/2" 3193' cem. w/110 sx

ELEVATION 1736 DF

PRODUCTION 60 BO & NW

FIGURES INDICATE BOTTOM OF FORMATIONS

shale & red bed	225
sand streaks	250
shale & shells	269
lime	278
sand, shale & red bed	465
red bed	600
anhydrite	630
red bed	820
shale & shells	1275
lime & shale	1880
lime, shale & shells	2165
shale	2285
shale & lime	2455
shale & shells	2570
lime	2675
lime & shale brks	2745
lime	2805
lime & shale	2875
lime	3180
conglomerate	3191
arbuckle	3193
arbuckle lime	3200
Total Depth	

Scout Tops:

Heebner	2774
Toronto	2790
Douglas	2806
Lansing	2865
Conglomerate	3185
Arbuckle	3192

Cable Tool Drilling Report:
3195'-3200': Show of oil.
Producing 15 bbls. per hr.