

33-15-11W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

ROBINOWITZ OIL COMPANY &
Company- PETROLEUM OPERATING COMPANY
Farm- Davidson No. 1

SEC. 33 T. 15 R. 11W
SW NW SW

Total Depth. 3284'
Comm. 10-8-62 Comp. 10-17-62
Shot or Treated.
Contractor. Sholom Drilling Co., Inc.
Issued. 3-9-63

County Russell
KANSAS



Elevation. 1830' KB

Production. 25 BOPD

CASING:

8 5/8" 308' cem w/175 sx.
5 1/2" 3278' cem w/100 sx.

Figures Indicate Bottom of Formations.

clay	35
post rock & clay	70
shale & clay	100
shale	230
sand & shale	290
plug & cement	308
blue shale & sand streaks	370
sand	395
hard sand & pyrite	421 ✓
sand & shale	440
shale & sand	480
red bed	684
anhydrite	710
shale & shells	1350
lime & shale	2590
lime	3240
lime, shale & chert	3275
shale	3276
arbuckle	3284 RTD
Total Depth	

TOPS:

Anhydrite	684 - 710
Topeka	2616
Heebner	2855
Toronto	2873
Douglas	2887
Brown Lime	2946
Lansing	2955
Base Kansas City	3201
Conglomerate	3249
Simpson	3271
Arbuckle	3276

DST #1 2957-3010' Rec. 30' drilling mud.

DST #2 3278-3284' Rec. 850' oil.

DST #3 2798-2994' (Straddle) at T.D. 3284'
Rec. 380' gas cut mud.