

33-15-11W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

ROBINOWITZ OIL &
Company- PETROLEUM OPERATING CO.
Farm- Davidson No. 3

SEC. 33 T. 15 R. 11W
NW SW SW

Total Depth. 3289'
Comm. 3-9-63 Comp. 3-18-63
Shot or Treated.
Contractor. Sholom Drig. Co., Inc.
Issued. 7-27-63

County Russell
KANSAS



Elevation. 1819' KB

Production. 100 BOPD, NW

CASING:

8 5/8" 309' cem w/175 sx.
5 1/2" 3288 1/2' cem w/100 sx.

Figures indicate Bottom of Formations.

surface hole	307	
shale, shells & sand	398	DST #2 2858 - 2961' Rec. 130' muddy water,
hard sand	415	SI GC
shale & sand streaks	490	
red bed	668	DST #3 2956 - 3143' Rec. 480' muddy water.
anhydrite	715	
red bed	934	DST #4 3234 - 3289' Rec. 60' OCM, 60' HOCM,
red bed - salt, shale & shells,		180' VHOCM, 600' muddy oil
sandy lime strk.	1370	
shale & lime	1710	
sand	1790	
shale & lime	2180	
sandy lime & shale	2390	
shale & shells	2580	
shale & lime	2653	
sand & shale	2735	
lime & shale	2835	
lime	2910	
shale & lime	2961	
lime	3002	
lime & shale	3085	
lime	3145	
lime & shale	3150	
lime	3275	
lime, conglomerate & arbuckle	3289	RTD
Total Depth		

TOPS:

Anhydrite	668 - 715
Topeka	2607
Plattsmouth (Sample)	2792
Heebner	2851
Toronto	2863
Douglas	2882
Lansing	2942
Base Kansas City	3195
Conglomerate	3242
Arbuckle	3283

DST #1 2784 - 2840' Rec. 135' muddy water.