

33-15-11W


H. H. BLAIR ET AL
Foster No. 1.

SEC. 33 T. 15 R. 11W
CSL SE SE

DEEPENING RECORD.

Total Depth. 3285
Comm. 4-25-41 Comp. 6-16-41
Shot or Treated.
Contractor. M.B. Armer
Issued. 8-15-42

County. Russell



CASING:

12 1/2" 277'
10" 642'
8 1/4" 1937' UR 2352'
7" 2995'
5 1/2" 3186' **Figures** Indicate Bottom of Formations.

Elevation.

Production. Pot. 60 B.
(min. well)

cellar	8	lime	1845	shale	2903
shale	12	shale	1850	lime	2908
lime	20	lime	1865	shale	2910
shale 1/8 BW	145	red rock	1870	lime	2911
red rock	150	lime	1880	shale red	2913
shale brwn	200	shale & shells	1890	lime	2942
shale lgt	210	red rock	1895	shale blk	2945
red rock	215	lime	1905	lime gas@2950	2977
shale	260	red rock	1920	shale & shells	2995
sand 20 BW	275	lime	1950	sm sh oil 2973-77	
shale	277	shale & shells	1985	lime (more oil 3000-05)	3008
shale sdy	360	shale	2000		
sand	370	red rock	2002	Total Depth.	
shale blue	445	shale	2005		
red rock	625	lime	2020		
lime & gyp	630	shale	2030		
anhydrite lime	663	shale & shells	2045	Top Kansas City 2903	
red rock	830	lime brkn	2060		
shale blue	900	shale & shells	2100		
red rock	950	lime brkn	2110		
shale blue	1070	shale & shells	2145		
salt	1275	lime	2150	<u>DEEPENING RECORD.</u>	
shale & salt shells	1315	shale	2175		
shale & shells	1335	lime	2185 ?	Comm. 7-4-42	
lime	1365	shale	2195	Comp. 7-25-42	
shale & shells	1375	lime	2200	Prod. Dry 5 1/2" 3196	
lime	1385	shale & shells	2220	lime 3039	
shale & shells	1395	lime	2225	More wtr 3023-33	
lime	1405	shale	2230	lime broken 3064	
shale blue & red	1410	red rock	2235	lime 3125	
lime	1425	shale	2240	shale 3130	
red rock	1435	lime	2245	shale 3155	
lime	1440	shale	2290	shale 3158	
shale	1450	lime	2295	lime 3177	
lime	1465	lime brkn	2305	shale 3182	
shale lgt	1490	shale	2345	lime 3199	
lime	1535	lime 2BW 2320-25	2365	conglomerate 3243	
red rock	1540	shale & shells	2385	quartzite & sand 3250	
shale	1550	lime	2400	sh oil 3245-50	
lime	1580	shale	2405	quartzite 3260	
shale	1585	shale & shells	2420	quartzite, sand 3269	
lime brkn 1/8 BW	1635	lime	2435	granite wash 3269	
shale	1645	shale	2485	red shale, sand	
lime	1655	shale & shells	2520	chert congl. 3271	
lime brkn	1675	lime	2545	Arbuckle lime	
lime sdy 2 BW	1685	shale	2557	dolomite 3272	
lime	1695	little wtr 2610, sh gas 2625	2625	granite 3285	
shale	1700	lime	2670	Total Depth.	
lime	1715	lime brkn	2680		
shale & shells	1730	lime	2820	Pulled casing & plugged.	
red rock	1740	little gas 2750-55			
lime	1760	shale	2830		
shale	1780	lime gas 2832	2840		
red rock	1790	red rock	2844		
lime	1805	shale	2855		
shale	1810	shale sdy	2865		
red rock	1815	lime 2BW 2855-60	2873		
lime	1830	red rock	2875		
red rock	1835	shale & shells	2885		