


33-15-11W

H. H. BLAIR
Foster "B" No. 1.

SEC. 33 T. 15 R. 11 W
CN 1/2 NE SW

Total Depth. 3269'
Comm. 10-31-41 Comp. 12-6-41
Shot or Treated.
Contractor.
Issued. 1-31-42

County. Russell



CASING:

12 1/2" 381' P 7" 3020' P
10" 645' LI 5 1/2" 3264' Cem.
8 1/4" 2320' P

Elevation.

Production. Pot. 233 B.

Figures Indicate Bottom of Formations.

cellar	10	red rock	1840	shale	3190
clay	20	lime	1865	lime	3210
shale blue	105	red rock	1870	shale	3213
red rock	130	lime	1895	lime	3220
shale blue	150	red rock	1900	conglomerate	3230
red rock	175	lime	1910	lime brkn	3250
shale	190	red rock	1925	lime	3252
red rock	215	lime	1965	shale green	3253
shale lgt	225	shale & shells	1995	lime	3265
red rock	285	red rock	2000	(lgt sh oil 3253-60)	
sand HFW	305	lime	2010	(oil pay 3265-69)	
shale blue	315	red rock	2015	(2500' oil in hole)	
sand	360	lime	2035	lime	3269
shale blue	386	shale	2045	Total Depth.	
lime	390	lime	2100		
shale blue	440	shale	2110		
red rock	565	lime	2125	Temp. Swbg test 48 bbls.	
iron brkn	575	shale	2155		
red rock	639	lime	2160		
lime anhydrite	670	shale	2165		
red rock	855	lime	2170		
shale	920	shale	2180		
red rock	963	lime	2205		
shale blue	987	shale & shells	2220		
red rock	995	lime	2240		
shale blue	1075	red rock	2250		
salt	1280	lime	2255		
salt & shale brks	1295	shale	2305		
salt	1305	lime	2330		
shale	1315	shale	2370		
lime	1335	lime (LBWPH 2355-60)	2400		
shale	1340	shale	2410		
lime	1365	lime	2430		
shale	1375	shale	2435		
lime	1395	lime	2455		
shale	1400	shale	2470		
lime	1410	lime	2480		
shale	1415	shale	2490		
lime brkn	1430	lime	2505		
red rock	1440	shale	2510		
lime	1465	lime	2525		
shale	1470	shale	2535		
lime	1490	lime	2540		
shale	1500	shale	2545		
lime	1530	lime	2570		
shale	1540	shale (1/2 BW 2630-40)	2578		
red rock	1555	lime Topeka	2850		
lime (1/2 BWPH 1565)	1570	shale (1/2 BW 2665-75)	2858		
shale	1600	lime	2870		
lime	1615	red rock	2875		
lime brkn	1675	shale	2905		
lime sft	1685	lime	2915		
lime (LBWPH 1675-85)	1695	shale	2942		
red rock	1710	lime Lans-K.C.	2998		
lime brkn	1755	shale 8BWPH	3000		
shale	1760	lime (oil 3020-27)	3072		
lime	1780	test 1 BO, 1 1/2 BWPH			
red rock	1795	shale blk	3075		
lime	1810	lime	3130		
shale	1815	shale	3133		
lime	1835	lime	3185		