

33-15-11W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY DUKE DRILLING

SEC. 33 T. 15 R. 11W
 LOC. SW SE SW

FARM Foster "B"

NO. 1

COUNTY Russell

TOTAL DEPTH 3286'


COMM. 9-15-67

COMP. 9-21-67

SHOT OR TREATED

CONTRACTOR Duke Drilling

ISSUED 1-20-68



CASING

20	10	
15	8 5/8" 481'	cem w/ 250 sx
12	6	
13	5 1/2" 3278'	cem w/ 100 sx

ELEVATION 1804' KB

PRODUCTION 8 BOPD, ARB

3278-86

FIGURES INDICATE BOTTOM OF FORMATIONS

0	-	39'	Clay
39	-	60'	Clay - lost Rocks
60	-	340'	Shale & Clay
340	-	343'	Sand
343	-	395'	Shale
395	-	419'	Sand
419	-	465'	Shale
465	-	657'	Red Bed
657	-	682'	Anhydrite
682	-	913'	Red Bed
913	-	1300'	Shale & Shells
1300	-	2050'	Lime & Shale
2050	-	2625'	Shale & Lime
2625	-	2835'	Lime
2835	-	2839'	Shale
2839	-	2856'	Lime Shale
2856	-	2867'	Lime
2867	-	2928'	Shale
2928	-	2943'	Lime Shale
2943	-	3185'	Lime
3185	-	3225'	Shale - lime
3225	-	3263'	Conglomerate
3263	-	3281'	Dolomite
	-	3286'	ARB

ELEVATION: 1804 K.B.

FORMATION DATA

Anhydrite	657
Heebner	2835
Brown Lime	2928
Lansing	2943
Conglomerate	3225
Arbuckle	3263
R.T.D.	3281

SURFACE CASING: Set 8-5/8" pipe at 481' with 250 sacks cement.

TOPS: SMP	
Anhydrite	657
Base anhydrite	682
Heebner	2835
Toronto	2856
Douglas	2867
Brown lime	2928
Lansing	2943
Base Kansas City	3185
Conglomerate	3225
Arbuckle	3263



AFFIDAVIT

STATE OF KANSAS
 COUNTY OF BARTON) ss.

L. O. Chubb, of lawful age, does swear that the statements and facts herein contained are true and correct to the best of his knowledge.

L. O. Chubb