

KANSAS GEOLOGICAL SOCIETY 34-15-11W
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY DUKE DRIG.

SEC. 34 T. 15 R. 11W
LOC. N/2 S/2 NE

FARM Pelz

NO. 3

TOTAL DEPTH 3339

COMM. 2-18-66

COMP. 2-25-66


SHOT OR TREATED

CONTRACTOR Duke Drlg.

ISSUED 5-14-66

COUNTY Russell

KANSAS



CASING

20 10
15 8 5/8" @ 343' w/190 SX.
12 6
13 5
4 1/2" @ 3338' w/75 SX.

ELEVATION 1864' KB

PRODUCTION 80 BOPD &
30 BWPD

FIGURES INDICATE BOTTOM OF FORMATIONS

Russell County, Kansas

0 - 45' Post Rock & Clay
45 - 500' Clay Shale Sand
500 - 724' Red Bed
724 - 755' Red Bed
755 - 1355' Red Bed Shales & Shells
1355 - 1630' Shale Lime Streaks
1630 - 2053' Lime & Shale
2053 - 2585' Lime Shale
2585 - 2895' Lime
2895 - 2899' Shale
2899 - 2912' Lime & Shale
2912 - 2924' Lime
2924 - 2983' Shale
2983 - 3290' Lime
3290 - 3319' Shale Lime Conglomerate
3319 - 3335' Sand
35 - 3339' Shale
3339 R.T.D.

ELEVATION: 1864'

FORMATION DATA

Anhydrite	724
Heebner	2895
Douglas	2924
Lansing	2999
Conglomerate	3290
Sand	3319
R.T.D.	3339

SURFACE PIPE: Set 8-5/8"
28' at 343' with 190 sacks
cement.

PRODUCTION PIPE: Set 4 1/2"
at 3338' with 75 sacks
common cement and 200 gals.
latex

TOPS: SAMPLE

Heebner	2895
Tinto	2912
Douglas	2924
Iatan	2984
Lansing	2997
Conglomerate Sand	3318

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

L. O. Chubb, of lawful age, does hereby swear that the facts
and statements herein contained are true and correct to the best of his
knowledge.