

34-15-11W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **DUKE DRILG, CO.**

SEC. 34 T. 15 R. 11W
 LOC. SE SE SW

FARM **Pelz**

NO. 4

TOTAL DEPTH **3298'**

COMM. 4-25-66

COMP. 5-2-66


SHOT OR TREATED

CONTRACTOR **Duke Drilg. Co.**

ISSUED **12-24-66**

COUNTY **Russell**

KANSAS



CASING

20	10	
15	8 5/8	332' w/190 sx cem.
12	6	
13	5 1/2	3288' w/125 sx cem.

ELEVATION **1860' K.B.**

PRODUCTION Pmp. 24 BOPD
 & 80% wtr (Arb 3288'
 98)

FIGURES INDICATE BOTTOM OF FORMATIONS

0 -	40'	Post Rock, Clay
40 -	527'	Shale
527 -	690'	Red Bed
690 -	730'	Anhydrite
730 -	1315'	Red Bed
1315 -	1570'	Shale & Shell
1570 -	1970'	Lime & Shale
1970 -	2170'	Shale- Lime
2170 -	2535'	Shale
2535 -	2730'	Lime & Shale
2730 -	2870'	Lime
2870 -	2874'	Shale
2874 -	2898'	Lime- Shale
2898 -	2958'	Shale
2958 -	2970'	Lime - Shale
2970 -	3256'	Lime
3256 -	3287'	Conglomerate
3287 -	3298'	Quartz
3298		RTD

Sec 34-15-11W
 Russell County, Kansas

ELEVATION: 1860 K.B.

FORMATION DATA

Anhydrite	696
Heebner	2870
Douglas	2898
Brown Lime	2958
Lansing	2970
Conglomerate	3256
Quartz	3287
RTD	3298

Toronto (SCOUT) 2888

SURFACE CASING: Set 8 5/8" casing at 332' with 190 sacks cement.

PRODUCTION CASING: Set 5 1/2" at 3288' with 125 sacks cement.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss.

L. O. Chubb, of lawful age, does swear that the facts and statements herein contained are true and correct to the best of his knowledge.