

34-15-11W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY DUKE DRILLING

SEC. 34 T. 15 N. 11W
LOC. NW NW NE

FARM Pelz-Schreiber NO. 5

TOTAL DEPTH 3350

COMM. 3-5-67

COMP. 3-12-67


SHOT OR TREATED

CONTRACTOR Duke Drlg.

ISSUED 5-6-67

COUNTY Russell

KANSAS



CASING

20	10
15	8 5/8" @ 325' w/175 SX
12	6
13	5 1/2" @ 3350' w/75 SX

ELEVATION 1850' KB

PRODUCTION PMP 15 BOPD/NW
CONG SD 3312-18

FIGURES INDICATE BOTTOM OF FORMATIONS

0 -	120'	Shale Clay Sand
120 -	325'	Shale Sand Red Bed
325 -	709'	Red Bed
709 -	738'	ANHYDRITE
738 -	1565'	Shale Shells
1565 -	2140'	Line Shale
2140 -	2460'	Shale & Shells
2460 -	2600'	Line & Shale
2600 -	2887'	Line
2887 -	2891'	Shale
2891 -	2905'	Line Shale
2905 -	2916'	Line
2916 -	2980'	Shale & Sand
2980 -	2994'	Brown Line
2994 -	3282'	Line
3282 -	3350'	Conglomerate

Russell County, Kansas

ELEVATION: 1850 K.B.

FORMATION DATA

Anhydrite	709
Heebner	2887
Brown Line	2980
Lansing	2994
Conglomerate	3282
RTD	3350

SURFACE CASING: Set 8-5/8"
at 325' with 175 sacks cement

PRODUCTION CASING: Set 5 1/2"
used at 3350' with 75 sacks
cement & 200 gal. latex.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

L. O. Chubb, of lawful age, does swear that the facts and
statements herein contained are true and correct to the best of
his knowledge.

L O Chubb