

DRILLER'S WELL LOG

DATE COMMENCED: 5-10-76
DATE COMPLETED: 5-16-76

Leo G. Wetherill Jr.
Peschka #2
S $\frac{1}{2}$ NW NE, Sec. 34-15S-11W
Russell County, Kansas

ELEVATION: 1849 K.B.
1843 G.L.

0- 315' Shale
315- 702' Shale & Sand
702- 737' Anhydrite
737-1360' Shale
1360-1500' Shale w/lime streaks
1500-2622' Lime & Shale
2622-2858' Lime
2858-2899' Lime & Shale
2899-2910' Lime
2910-2972' Sand & Shale
2972-2986' Lime & Shale
2986-3260' Lime
3260-3278' Lime & Shale
3278-3306' Shale, Lime, Chert, Sand
3306-3330' Cong. sand
3330-3370' Lime
3370' RTD

FORMATION DATA

Anhydrite	702
Heebner	2880
Toronto	2899
Douglas	2910
Brown Lime	2972
Lansing	2986
Base K.C.	3260
Conglomerate	3278
Cong. Sand #1	3306
Cong. Sand #2	3322
RTD	3370

SURFACE PIPE:
Set 306' of 8 5/8", 28#
used pipe w/175 sacks Common
2% Gel, 3% cc.

PRODUCTION PIPE:
Ran new 10#, 4 1/2" casing
@ 3369' w/50 sacks Common.

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Glenn J. Bishop, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Handwritten initials/signature