

3-15-12W

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - HARRY GORE
Farm - Soukup

No. 6

SEC. 3 T. 15 R. 12W
SW NW SW

Total Depth. 3060'

Comm. 1-15-47


Shot or Treated.

Contractor.

Issued. 4-12-47

Comp. 3-12-47

County. Russell
KANSAS



Elevation. 1835 ft

Production. 250 bbls. per day

CASING:
12 1/2" 460' 7" 2934' UR 3002' Cem. w/100sx
10 3/4" 722' Cem. w/550 sx
8-5/8" 2044' UR 2315' 5 1/2" 3048'

Figures Indicate Bottom of Formations.

cellar	0-10	shale	2480
post rock & clay	35	lime	2485
shale blue	200	shale	2500
lime	205	lime	2515
shale	215	shale	2570
red rock	225	lime	2590
shale	250	shale	2595
sand	265	shale & shells	2615
shale blue	460	lime	2635
red rock	712	shale	2645
anhydrite lime	745	lime	2725
red rock	925	shale	2735
shale blue	970	lime	2880
red rock	1020	shale blk	2882
shale blue	1120	lime	2885
salt	1355	shale blue	2892
shells & shale	1490	Dodge lime	2916
red rock	1495	red rock	2920
lime	1505	shale blue	2934
shale & shells	1650	shale sdy	2960
red rock	1660	shale	2969
lime	1785	K. C. lime	2980
shale	1795	lime hrd	3002
red rock	1800	lime sft Oil	3011
lime	1850	lime hrd	3028
shale	1860	shale	3032
lime	1870	lime	3044
red rock	1880	shale	3048
lime	1890	lime hrd	3050
shale	1905	sft lime Oil	3058
lime	1930	lime	3060
red rock	1935	Total Depth	
shale & shells	1975		
lime	1980		
red rock	1990		
lime	2000		
shale & shells	2025		
lime	2047		
shells & shale	2095		
lime	2125		
shale & shells	2145		
shale	2245		
shale & shells	2255		
shale	2295		
lime	2300		
shale	2315		
lime	2320		
shale	2325		
red rock	2322		
corr. in measurement:			
2325=2320			
lime	2325		
shale & shells	2400		
shale	2435		
lime	2455		
shale	2460		
lime	2475		

Water Record:

HPW	250-260
1/8 BWPH	1610-1620
1/8 BWPH	2765-2775
3 BWPH	2910-2916

Sand Record:

lime show of gas	2735-85
lime show of oil	2830-40
sft lime show of	
oil & gas	3002-11
sft lime oil	3050-58
Good Sat. & Por.	3050-58'