

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

3-15-12W


Company BRUNSON ET AL
Farm Steinle No. 1

SEC. 3 T. 15 R. 12W
SW NW SE

Total Depth. 3253'
Coring. 11-26-44
Shot or Traced.
Contractor
Issued. 7-17-48

Comp. 1-9-46

County. Russell
KANSAS



CASING:
15" 39' 7" 2940'
10" 683' 5" 3111'
8" 2393'

Elevation. _____

Production. 18 BO & 20 BW

Figures indicate Bottom of Formations.

cellar	9	shale & shells	2185
clay yellow	20	shale	2215
shale brwn	35	lime	2225
shale	95	red rock	2240
shale sdy	115	shale & shells	2375
shale	130	lime	2405
red rock	175	shale & shells	2520
shale	210	lime	2580
sand	220	shale	2583
shale	260	lime	2590
sand	265	shale	2595
shale	400	lime	2700
shale	410	shale	2710
shale red	425	lime	2740
red rock	500	shale	2745
shale	510	lime	2875
red rock	677	shale brwn	2897
anhydrite & lime	684	lime	2900
lime	715	shale sdy	2920
red rock	880	shale brwn	2937
shale	930	lime brwn	2950
red rock	985	no log	3253
shale	995	Total Depth	
lime	1000		
shale	1100	S.S.O. 2674-80	
salt	1325	1 BW 125	
shale	1375	HFW 220	
lime	1380	$\frac{1}{2}$ BW 1625	
shale & shells	1400	$\frac{1}{4}$ BW 2655-60	
lime	1510	BW 2825-35	
shale	1520		
lime	1565	Top of Kansas City	2937
shale	1590	Very small show oil	2965-75
lime	1600	Trace free oil	3005-14
lime brwn	1625	Oil	3025-31
lime	1785	S.D. $1\frac{1}{2}$ hrs. made $1\frac{1}{3}$ bailers	
shale & shells	1820	free oil every 30 minutes.	
lime	1870	Deepened to 3031-33 good sat.	
red rock	1880	Deeper 3033-35- last foot shale	
lime	1885	Well S.D. for 1 hr. made 1 BOPH.	
shale	1890	T.D. 3036	
lime	1910	Show 1 BOPH	
red rock	1925	P.B. 3019 Bailed $3\frac{1}{4}$ BO & 2 BWPH.	
lime	1940	acid. w/5000 gals.	
lime shells &		Show 1 BO to 3036.	
shale	1965	Sdy Conglomerate	3110
shale & shells	1985	T.D.	3253
lime	2000	HFW Gorham	3230
shale	2010	Testing F.U. 500' water.	
lime	2020	S.S.O. 12 hrs. P.B. 2985	
shale	2028	Perf. 2958-81. F.U. 300'-12 hrs.	
Red rock	2040	Pmping 26 BO & 26 BW in 24 hours.	
shale & shells	2080	Pmp. 18 BO & 20 BW P.P.	
lime	2100		
shale & shells	2162		
shale	2175		