

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bldg, Wichita, Kansas.

Plotted per


3-15-12W

CITIES SERVICE OIL CO.
Zeman No. 1

SEC. 3 T. 15 R. 12W.
SW¹/₄ NW
330' N 330' E of W¹/₄ cor.

Total Depth. 3250
Comm. 8-24-41 Comp. 9-14-41
Shot or Treated. None.
Contractor. Corbett & Barbour Drlg. Co.
Issued. 10-18-41

County Russell.



CASING.

85/8" 312' cemented.
5 1/2" 3222' cemented.

Elevation.

Production. Pot. 3102 B.
no wtr. Echometer.

Figures Indicate Bottom of Formations.

surface soil	30
shale sand & shells	235
shale and shells	312
shale sand shells and iron	500
red bed	685
anhydrite	720
shale and shells	1125
salt and shells	1315
lime	1515
shale and lime shells	1695
lime and shale	1770
lime	2010
shale and shells	2160
shale	2280
lime	2290
shale	2539
shale and shells	2650
lime	2915
shale	2931
lime	3107
shale	3120
lime	3180
shale and lime	3217
sand	3221
3221 Rot T.D. equals 3225 SIM	
sand	3250
Total Depth.	

Top Kansas City 2930
Corr. Top Gorham sand 3222
Penetration 28'

show of oil 2996-78
show oil 3028-35

FILLUP. 100' oil in 1 1/4 hours 3235
350' oil in 3 1/4 hours 3241
1300' oil in 4 1/4 hours 3245