

4-15-12W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Cook No. 7

SEC. 4 T. 15 R. 12W
SE NE SE
990' S. and 330' W. of E/4
Corner.
County. Russell

Total Depth. 3297' S.L.M.
Comm. 3-11-47 Comp. 8-23-47
Shot or Treated. 2000 gal. 3100-3122. 5000 gal. 3021-94, 8-29&30
Contractor. Corbett & Barbour Drilling Co.
Issued. 10-25-47

KANSAS



Elevation. 1867 *act & rh*

CASING:
8-5/8" 492' Cem. W/250 Sx.
5-1/2" 3296' Cem. W/175 Sx.

Production. Pmup 29 oil, 16

Figures Indicate Bottom of Formations. wtr., 24 hours (3-5-47).

Rock & clay	40
shale & shells	484
red bed	492
red bed & shale	740
anhydrite	773
shale & shells	1155
shale, shells, & salt	1370
shale & shells	1675
shale & lime	1865
lime & shale	1955
shale & lime	2340
shale	2470
shale & lime	2705
lime	2950
lime & shale	3010
lime	3295

3295 Rotary T.D. - 3297 S.L.M.

TOPS:

Lansing	3010'
Reagan	3295
Penetration	2'
Total Depth	3297'

Drilled Cem. to 3273 S.L.M.

Perforated 72 shots 3100-3122
" 48 shots 3081-94
" 17 shots 3021-25

Set packer at 3095 & acidized
3100-3122 W/2000 gallons.
Acidized 3021-25 & 3081-94
with 3000 gallons.

7-7/8" Rotary Hole.


Company - CITIES SERVICE OIL CO.
Farm - Cook No. 7

4-15-12W
SEC. 4 T. 15 R. 12W
SE NE SE
990' S. and 330' W. of E/4
Corner.
County. Russell

DEEPENING RECORD

Total Depth. 3307'
Comm. 3-11-47 Comp. 8-23-47
Shot or Treated. 2000 gal. 3100-3122. 3000 gal. 3021-94, 8-39&30
Contractor. Corbett & Barbour Drilling Co.
Issued. 7-7-51

KANSAS



Elevation. _____

Production. Pump 29 oil, 16

Figures Indicate Bottom of Formations. wtr., 24 hours (3-5-47).

Rock & clay	40
shale & shells	484
red bed	492
red bed & shale	740
anhydrite	773
shale & shells	1155
shale, shells, & salt	1370
shale & shells	1675
shale & lime	1865
lime & shale	1935
shale & lime	2340
shale	2470
shale & lime	2705
lime	2950
lime & shale	3010
lime	3295

3295 Rotary P.D. - 3297 S.L.M.

TOPS:

Hansing	3010'
Reagan	3295
Penetration	2'
Total Depth	3297'

Drilled Cem. to 3273 S.L.M.

Perforated 72 shots 3100-3122
" 48 shots 3081-94
" 17 shots 3021-25

Set packer at 3095 & acidized
3100-3122 W/2000 gallons.
Acidized 3021-25 & 3081-94
with 3000 gallons.

7-7/8" Rotary Hole.

DEEPENING RECORD

By Cities Service Oil Co.
Comm. 1-10-51
Comp. 1-10-51
I. P. pump 107 BO & NW
in 14 hrs.
1100 3307
Total Depth