

4-15-12W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.


SEC. 4 T. 15 R. 12W

FARM Cook NO. 10

LOC. SW SE SE
990' W & 330' N of SE cor.

TOTAL DEPTH 3323 PB 3218
COMM. 8-15-50 COMP. 9-10-50
SHOT OR TREATED
CONTRACTOR J.W. Braden Drlg Co.
ISSUED 12-16-50

COUNTY Russell



CASING

8 5/8" 727' cem w/400 sx.
5 1/2" 3296' cem w/110 sx.

ELEVATION 1858

PRODUCTION Pmp 151 bbls oil
/ 109 wtr

FIGURES INDICATE BOTTOM OF FORMATIONS

clay, shale	115
shale, shells	255
sand	285
shale, shells	405
sand	465
shale	475
shale, shells	505
red bed	722
anhydrite	780
shale, shells	1200
salt	1360
lime, shale	1740
lime	1990
lime, shale	2125
lime	2240
lime, shale	2605
shale, shells	2685
lime	3075
lime, shale	3115
lime	RTD 3300
3300 RTD = 3298 SLM	
sand	3323
Total Depth	
Plugged back to	3218

Tops: Corr.
Lansing 3003
Gorham 3295
Penetration 28

305' water in 2 hrs. 40 mins.
2000' " " 19 hrs.

Set Baker plug @ 3229';
lumped 1 sack cement on
plug; PB 3218 SLM

10 gals. water with small
show oil in 1 hr.

Perf: 51 shots 3094-3108
" 18 " 3073-78
" 14 " 3033-45

Elevation 1855 Gr.