


Plotted
4-15-12W p. 2 f.
SEC. 4 T. 15 R. 12W
NEC SW

CENTRAL PETRO. CO., INC.
Kuhle No. 1.

Total Depth. 3067'
Comm. 7-8-38 Comp. 8-6-38
Shot or Treated.
Contractor. Harry Gore
Issued. 8-20-30

AUG 20 1938

County. Russell



Elevation.

CASING:
12 $\frac{1}{2}$ " 452' 6 5/8" 3060'
10 " 753'
8 $\frac{1}{4}$ " 2386'

Production. Pot. 551 Bbls.

Figures Indicate Bottom of Formations.

cellar	10	lime	1850	shale	2505
clay	30	shale blue	1855	shale blue	2515
shale blue	145	lime	1870	lime	2535
shale lgt	165	red rock	1885	shale blue	2540
shale sdy	185	lime	1895	lime	2545
shale blue	225	shale blue	1905	shale blue	2555
red rock	230	red rock	1915	slate & shells	2600
shale grey	255	lime	1950	lime	2605
shale sdy	275	shale blue	1965	shale blue	2615
shale blue	290	lime	1975	lime	2760
red rock	310	shale brown	1980	shale blue	2765
shale blue	355	lime shell	1982	lime	2790
sand wtr	360	red rock oave	2005	shale blue	2793
shale blue	385	lime	2010	lime	2898
sand wtr	425	lime brkn	2025	shale blue	2908
shale blue	456	shale & shells	2040	lime Dodge	2925
lime	460	lime	2047	shale brown	2928
shale sdy	475	shale	2050	shale & lime brkn	2979
red rock	743	lime	2085	lime Oswald	2984
lime anhydrite	780	red rock	2090	shale	2992
red rock	960	lime	2095	lime hrd	2997
shale blue	1005	shale blue	2100	lime sft	2999
red rock	1055	lime	2120	lime hrd	3015
shale blue	1150	shale blue	2135	lime sdy	3025
salt	1400	lime	2145	lime med	3030
shale blue	1410	shale	2150	lime hrd	3037
lime	1420	lime	2160	lime sft	3040
shale blue	1430	shale & shells	2185	lime hrd	3050
shale & shells	1450	shale blue	2195	shale sft	3054
lime	1475	shale & shells	2270	lime hrd	3058
shale blue	1478	shale blue	2275	shale blue	3060
lime	1490	lime	2290	lime med	3062
shale blue	1500	shale blue	2310	lime Oil	3067
shale & shells	1535	lime	2317	Total Depth.	
lime	1570	red rock	2323		
shale blue	1595	shale sdy	2370	$\frac{1}{2}$ BW 255-75	$\frac{1}{2}$ BW 2860
lime	1635	shale blue	2383	4 BW 460-75	2 BW 3015-25
red rock	1650	shale & shells	2410	$\frac{1}{2}$ BW 1655-70	Water 2928-79
lime	1690	shale	2435	3 BW 2010-25	
shale lgt	1695	shale blue	2445		
lime	1790	lime	2473	Lime Dodge 2908-2925	sh gas
shale blue	1795	shale blue	2478	Lime Oswald 2979-2984	Pay
red rock	1800	lime	2490		