

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bldg., Wichita, Kansas


5-15-12W

CITIES SERVICE OIL CO.
 Schartz No. 2.

SEC. 5 T. 15 R. 12W
 CWL SE NE
 660' N 990' W of E $\frac{1}{4}$ Cor.

Total Depth. 3239'
 Comm. 7-5-41 Comp. 7-24-41
 Shot or Treated. None
 Contractor. Corbett-Barbour Drlg. Co.
 Issued. 9-6-41

County. Russell



CASING:
 8 5/8" 315' Cem.
 5 1/2" 3229' Cem.

Elevation.

Production. Phy. Pot. 277 B.
 1% Wtr

Figures Indicate Bottom of Formations.

surface	40
shale & shells	305
shale	315
shale & shells	400
red bed	460
shale & red bed	665
shale & shells	690
anhydrite	730
shale & shells	868
shale	960
salt	1230
shale & shells	1445
lime	1550
lime brkn	1570
lime	1650
shale	1705
lime & shale	1800
lime	1873
shale & shells	2135
lime	2175
lime brkn & shale	2204
shale & shells	2272
shale	2340
lime	2370
shale	2401
lime	2444
shale	2563
shale & shells	2645
lime	3225
sand	3226
3226 Rot. TD=3229 SIM	
sand (pay 3233-39)	3239
Total Depth.	

Corr. Top Gorham 3228
 Penetration 11

Fillup:
 375' oil in 1 $\frac{1}{2}$ hrs
 1000' oil in 2 $\frac{3}{4}$ hrs
 1500' oil in 4 hrs
 1700' oil in 6 hrs

2100' oil in 10 hrs