

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


5-15-12W

Company- N. V. MAYBRIER
Farm- Vejl No. 1

SEC. 5 T. 15 R. 12W
NE NW SW

Total Depth. 3277'
Comm. 5-25-54 Comp. 6-7-54
Shot or Treated.
Contractor. Shields Drlg. Co., Inc.
Issued. 7-10-54

County Russell
KANSAS



CASING:

8 5/8" 237' cem w/150 sx
5 1/2" 3274 1/2' cem w/75 sx

Elevation. 1830' DF

Production. 50 BOPD no wtr.

Figures Indicate Bottom of Formations.

top soil & clay	5
post rock	20
shale & shells	190
shale & red bed	495
red bed	760
anhydrite	790
shale & red bed	1130
shale & salt	1200
shale & shells	1375
shale & lime streaks	1480
lime & shale	1970
shale	2075
lime & shale	2320
shale & sand	2455
shale & lime streak	2560
lime & shale	2999
lime	3278
Arbuckle lime	3280
Corrected to	3277
Total Depth	

Tops:

Anhydrite	760
Tarkio Sand	2353
Tarkio Lime	2402
Topeka	2675
Heebner	2913
Toronto	2931
Lansing-Kansas City	2996
Arbuckle	3274

DRILL STEM TESTS:

#1 3015-40, open 1 hr., rec. 10' mud,
no oil shows, 50# BHP/20 minutes.