

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


6-15-12W

Company- SHIELD OIL PRODUCERS, INC.  
Farm- Hupfer No. 3

SEC. 6 T. 15 R. 12W  
NW SE SE

Total Depth. 3300'  
Comm. 6-5-62 Comp. 6-12-62  
Shot or Treated.  
Contractor. Shields Drlg. Co.  
Issued. 9-15-62

County Russell  
KANSAS



CASING:  
8 5/8" 280' cem w/180 sx.

Elevation. 1828' RB

Production. Dry

Figures Indicate Bottom of Formations.

clay & shale	280
shale, shells & redbed	700
red bed	766
Anhydrite	792
shale & lime streaks	1265
lime & shale	2745
lime	3300 RTD
Total Depth	

TOPS:	
Anhydrite	766
Heebner	2906
Toronto	2924
Lansing-Kansas City	2990
Cherty Conglomerate	3266
Arbuckle	3296

DST #1 3192-3220', op 1 hr w/weak blow  
thruout. Rec. 15' OCM & 15 mud.  
IBHP 1001#/ IFP 11#, FFP 33#, FBHP 89#/20 min.