

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas


6-15-12W

Company- THE TEXAS COMPANY
 Farm- S. K. Steinert No. 3

SEC. 6 T. 15 R. 12W
 NE NE NW

Total Depth. 3202 PB 2960
 Comm. 8-4-52 Comp. 9-10-52
 Shot or Treated.
 Contractor. Stickle Drlg. Co.
 Issued. 10-18-52

County Russell
 KANSAS



Elevation. 1734 DE

Production. 32 B0 & 14 BW

CASING:

8 5/8" 691' cem. w/400 sx circ.
 5 1/2" 3050' cem. w/80 sx

Figures indicate Bottom of Formations.

surface clay	60
sand	75
shale	100
shale & shells	375
red bed	682
anhydrite	715
shale & shells	1450
lime & shale	1940
shale & shells	1995
lime & shale	2095
shale & shells	2180
shd e	2196
sand	2198
shale & sand	2228
shale	2240
shale & sand	2372
shale & lime	2384
shale & shells	2590
lime brkn & shale	2625
lime	2822
heebner shale	2848
douglas shale	2898
brown lansing	2920
lansing lime	2945
lime	3060
lime hrd	3096
lime	3180
conglomerate	3197
arbuckle	3202
Total Depth PB	2960

Tops:

Toronto	2312
Topoka	2577
Heebner	2844
Brown Lansing	2895
Lansing	2908
Arbuckle	3197

Measurement from BH to KB
 7.84' BH to GL 2.15