

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

7-15-12W

COMPANY Three G. Oil, Inc.

SEC. 7 T. 15S R. 12W
LOC. S/2 N/2 SE/4


FARM Hilgenberg NO. 2

TOTAL DEPTH 3,328
COMM. March 13, 1967

COMP. March 22, 1967

COUNTY Russell

SHOT OR TREATED
CONTRACTOR H-30, Inc.
ISSUED 5-20-67



CASING

20	10	
15	8 - 5/8"	354' Cemented with 200 Sx
12	6	
13	5 - 1/2"	3246' Cemented with 125 Sx

ELEVATION 1859 KB

PRODUCTION 111 BOPD/NW
LKC 3087-94 Grav 40.5

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Beds & Surface Soil	100	ELECTRIC LOG TOPS:		
Shale, Sand & Pyrites	355	Anhydrite	784	+1075
Shale & Shells	781	Base Anhydrite	810	+1049
Anhydrite	809	Tarkio	2422	- 563
Shale & Shells	1115	Elmont	2479	- 620
Shale & Lime	1545	Howard	2620	- 761
Shale & Lime Streaks	1950	Topeka	2656	- 797
Lime & Shale	2305	King Hill	2775	- 916
Shale & Lime Streaks	2620	Queen Hill	2843	- 984
Shale & Lime	2835	Heebner	2930	-1071
Lime	3328	Toronto	2949	-1090
Rotary Total Depth	3328	Douglas	2963	-1104
		Brown Lime	3013	-1144
		Lansing-K.C.	3030	-1171
		Base K.C.	3260	-1401
		Conglomerate	3300	-1441
		Arbuckle	3312	-1453
		Log T.D.	3327	-1468
		Rotary T.D.	3328	-1469

I hereby certify the above and foregoing to be a true and correct log of the above described well, as shown by the drilling reports.

H-30, Inc.

By Arlo B. Romer
Arlo B. Romer

STATE OF KANSAS }
SEDGWICK COUNTY } SS:

Subscribed and sworn to before me, a Notary Public in and