

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COPY
7-15-12W

COMPANY Three G Oil, Inc.

SEC. 7 T. 15S R. 12W
LOC. Cen NW NE SE

FARM Hilgenberg NO. 4

TOTAL DEPTH ~~8x311'~~ 3321'

COUNTY Russell

COMM. May 26, 1967


COMP. June 5, 1967

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED 9-9-67

KANSAS



CASINO

20	10	
15	8-5/8"	324' cemented with 185 sacks ELEVATION 1,871 KB
12	6	
13	5-1/2"	3,311' cemented with 125 sacks

PRODUCTION 65 BOPD, NW
Arbuckle 3312-21 Gray 40

FIGURES INDICATE BOTTOM OF FORMATIONS

ELECTRIC LOG TOPS:

Limestone	45	Anhydrite	797	+1074
Post Rock	100	Base Anhydrite	825	+1046
Shale & Sand	324	Tarkio	2432	- 561
Shale	798	Elmont	2490	- 619
Anhydrite	829	Howard	2630	- 759
Shale & Red Bed	1088	Topeka	2666	- 795
Shale & Shells	1530	King Hill	2785	- 914
Lime & Shale	1585	Queen Hill	2852	- 981
Lime W/Shale Streaks	1800	Heebner	2937	-1066
Lime & Shale	2485	Toronto	2956	-1085
Lime	3319	Douglas	2971	-1100
Rotary Total Depth	3319	Brown Lime	3021	-1150
Drilled Deeper	3321	Lansing	3039	-1168
Total Depth		Base K.C.	3265	-1394
		Arbuckle	3307	-1436
		Log T.D.	3319	-1448
		Rotary T.D.	3319	-1448

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Arlo B. Romer

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss

Subscribed and Sworn to before me, a Notary Public in and for said county and state this 7th day of June, 1967.