

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

8-15-12W

COMPANY Three G Oil, Inc.

SEC. 8 T. 15S R. 12W
LOC. SE NW NW

FARM Herber NO. 1

TOTAL DEPTH 3,308'

COMM. 12-27-66

COMP. 1-10-67


SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED 4-1-67

COUNTY Russell

KANSAS



CASING

20 10
15 8-5/8" @ 268' w/160 sx. cement
12 6
13 5-1/2" @ 3304' w/50 sx. cement

ELEVATION 1854 KB

PRODUCTION PMP 134 BOPD, NW
ARB 3304-08

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay & Shale	268
Shale	400
Shale & Shells	809
Red Bed, Shale & Shells	1148
Shells & Shale	1465
Shale & Lime	3057
Lime	3308
Rotary Total Depth	3308

Electric Log Tops:

Anhydrite	778	+1076
B/Anhydrite	807	+1047
Tarkio	2420	- 566
Topeka	2654	- 800
Queen Hill	2838	- 984
Heebner	2923	-1069
Toronto	2941	-1087
Douglas	2956	-1102
Brown Lime	3007	-1153
Lansing	3027	-1173
Base/K.C.	3257	-1403
Arbuckle	3302	-1448
Log T. D.	3307	-1453
Rotary T. D.	3308	-1454

I hereby certify the above and foregoing to be a true and correct log of the above described well, as shown by the drilling reports.

H-30, INC.

By

Arlo B. Romer
Arlo B. Romer

STATE OF KANSAS }
SEDGWICK COUNTY } ss

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 13th day of January, 1967.

Maxine Lampe
Maxine Lampe - Notary Public

My Commission Expires:
December 27, 1967