

8-15-12W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Three G Oil, Inc.

SEC. 8 T. 15S R. 12W
LOC. NW SE NW

FARM Herber

NO. 2

COUNTY Russell

TOTAL DEPTH 3322'


COMM. February 22, 1967

COMP. March 4, 1967

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED 4-22-67



CASING

20	10	
15	8-5/8"	288' cemented with 175 sx.
12	6	
13	5-1/2"	3316' cemented with 100 sx.

ELEVATION 1867 KB

PRODUCTION POT 108 BOPD
NW NATL, ARB 3316-22

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay & Shale	70
Shale & Sand	288
Shale & Red Bed	425
Shale & Lime Streaks	782
Shale	817
Shale & Shells	930
Shale	1268
Lime	1277
Shale & Lime	1575
Lime	2045
Lime & Shale	2690
Lime	2756
Lime & Shale	2850
Lime	2930
Lime & Shale	3075
Lime	3322
Rotary Total Depth	3322

Electric Log Tops:

Anhydrite	778	+1089
Base Anhydrite	816	+1051
Tarkio	2435	- 568
Elmont	2499	- 632
Howard	2633	- 766
Topeka	2669	- 802
Queen Hill	2853	- 986
Heebner	2938	-1071
Toronto	2956	-1089
Douglas	2972	-1105
Brown Lime	3026	-1159
Lansing K C	3042	-1175
Base K C	3277	-1410
Arbuckle	3314	-1447
Log T. D.	3322	-1455
Rotary T. D.	3322	-1455

I Hereby certify the above and foregoing to be a true and correct log of the above described well, as shown by the drilling reports.

H-30, Inc.

By Arlo B. Romer
Arlo B. Romer

STATE OF KANSAS }
SEDGWICK COUNTY } ss:

Subscribed and sworn to before me, a Notary Public in and for said County and State, this 7th day of March, 1967.