

★
State Geological Survey
WICHITA BRANCH

2i
DRILLER'S WELL LOG

DATE COMMENCED: 9-17-80
DATE COMPLETED: 9-22-80

J. S. Martin Oil Operations
Kaufman B #1
NE NW SW Sec. 27-15-~~28~~W 12
Russell County, KS

ELEVATION: 1814' K.B.

FORMATION DATA

Anhydrite

2560-2596'	Lime
2596-2876'	Lime
2876-2881'	Shale
2881-2894'	Lime
2894-2909'	Lime
2909-2964'	Shale
2964-2977'	Lime & Shale
2977-3229'	Lime
3229-3250'	Lime & Shale
3250-3266'	Dolomite
3266'	RTD

Anhydrite

Howard	2560'
Topeka	2596'
Heebner	2876'
Toronto	2894'
Douglas	2909'
Brown Lime	2964'
Lansing Kansas City	2977'
Base Kansas City	3229'
Arbuckle	3250'
RTD	3266'

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1980

CONSERVATION DIVISION
Wichita, Kansas

SURFACE PIPE:

Set @ 252' 8 5/8" 28#
used casing w/165 sks
50/50 Pozmix 2% Gel
3% c.c.

PRODUCTION PIPE:

Ran 71 jts. 4 1/2" 14#
casing. Set @ 3265'
W/150 sks 50/50 Pozmix
18% salt 3/4 of 1% CFR2
20 bbls salt flush
P.D. 8:15 a.m.

A F F I D A V I T

STATE OF KANSAS }
C NTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis