

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL COMPANY
Farm - Zeman "B" No. 2

SEC. 9 T. 15 R. 12W
SE SW SE
330' N & 990' E of S $\frac{1}{4}$ corner

Total Depth. 3263'
Comm. 10-22-47 Comp. 11-7-47
Shot or Treated.
Contractor. Holm Drilling Company
Issued. 1-31-48

County. Russell
KANSAS



CASING:
8-5/8" 480' Cem. w/250 sx
5-1/2" 3248' Cem. w/125 sx
4-1/2" 3263' (liner) bottom 3' slotted

Elevation. _____

Production. Pumped 214 BO & 4
BW, 24 hours.

Figures Indicate Bottom of Formations.

clay & sand	0-90
shale	230
sand & iron shells	290
shale & shells	355
sand & iron	385
shale & shells	470
shale red	745
anhydrite	775
shale & shells	1175
salt & shale	1290
salt, shale & shells	1380
shale & shells	1410
lime & shale	2390
shale & shells	2480
shale & lime	2670
lime	2965
lime brkn	3015
lime	3250
sand	3252
3252 RTD= 3249' SLM	
sand	3263
Total Depth	

Tops:
Lansing corr. 2957
Gorham corr. 3247
Penetration 16

Fillup:
150' oil in $\frac{1}{2}$ hr. at 3263.
350' oil in 40 mins.
580' oil in 50 mins.
820' oil in 1 hr. 5 mins.
1030' oil in 1 hr. 20 mins.
2850' oil in 15 hrs.