


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - HARRY GORE
Farm - Kastrup No. 3.

SEC. 15 T. 15 R. 12 W
NWc SW

Total Depth. 3388
Comm. 2-10-46 Comp. 3-22-46
Shot or Treated.
Contractor. Harry Gore
Issued. 6-8-46

County. Russell
KANSAS



CASING:

12 1/2" 420' 7" 3015' reamed 3064' Elevation. _____
10" 695' 5 1/2" 3268' II Cem.
8" 2005' reamed 2408' Production. Dry

Figures Indicate Bottom of Formations.

cellar	9	shale blue & red	
soil & sand	25	rock	2895
shale blue	110	shale blue	2940
red rock	150	Kans. City lime	2970
water sand	160	shale blue	2975
shale blue	190	lime	3015
water sand	220	lime sft	3020
shale blue	230	lime	3034
red rock	265	lime	3062
shale blue	375	lime	3095
red rock	390	shale blue	3100
shale blk	420	lime	3150
red rock	685	shale blue	3158
anhydrite lime	715	lime	3175
red rock	900	shale blue	3185
shale blue	940	lime	3216
red rock	995	conglomerate	3231
shale blue	1100	lime shell	3232
salt	1335	Gorham sand	3240
shale blue	1350	Arbuckle lime	
lime	1460	some sand	3246
red rock	1465	hole filled up	
lime	1575	with water	
red rock	1580	lime Arbuckle	3332
lime	1840	chert, quartzite	
red rock	1845	granite wash	3384
lime brkn	1935	granite	3388
red rock	1950	Total Depth	
lime	2022		
lime brkn	2135	small show of oil	3020
shale blue	2150		
lime	2155		
shale blue	2165		
lime	2175		
shale blue	2225		
lime	2235		
shale blue	2260		
lime	2270		
shale blue	2340		
lime	2350		
shale blue	2360		
lime	2375		
shale blue	2400		
lime	2445		
shale blue	2455		
lime	2500		
shale blue	2540		
lime	2565		
shale blue	2570		
lime	2605		
shale blue	2610		
lime Topeka	2855		
shale blue	2865		
Dodge lime	2883		

Water Record

6 BW	150
HFW	190
4 BW	560-70
1/2 BW	1630
3 BW	1955-65
1/2 BW	2650
1 BW	2800-05
1/2 BW	2875-80
1 BWPH	3020
2 1/2 BW	3020-22
1/2 BW	3130-35
HFW	3246