


HARRY GORE ET AL
Miller No. 1.

SEC.15 T.15 R.12 W
NE SE NE

Total Depth. 2973'
Comm. 10-1-42 Comp. 10-31-42
Shot or Treated.
Contractor. Harry Gore
Issued. 12-12-42

County. Russell



CASING:

12 $\frac{1}{2}$ " 400'
10" 640' LI
8 $\frac{1}{4}$ " 2090' UD 2370'
7" 2881' UR 2962' LI
Cem.

Elevation.

Production. Pot.289 B.

Figures Indicate Bottom of Formations.

cellar	10	lime	2173
post rock	15	shale brown	2176
clay	30	shale & shells	2220
slate	80	shale blue	2265
shale yellow	85	lime	2280
red rock	95	shale & shells	2295
shale blue	105	shale blue	2325
sand wtr	110	lime	2337
red rock	130	shale blue	2340
shale lgt	150	lime	2355
red rock	160	shale blue	2365
shale blue	180	lime	2375
red rock	200	shale sdy	2457
shale blue	230	lime sft	2520
sand hd	238	lime	2530
shale blue	280	shale	2545
sand wtr	320	lime Topeka	2607
slate blk	330	shale blue	2610
iron & slate	340	lime	2789
slate blk	355	shale blk	2795
slate blue	365	lime Dodge	2801
red rock	628	shale & shells	2825
lime anh.	655	shale red	2830
red rock	840	shale blue	2843
shale blue	870	lime	2848
red rock	940	shale blue	2878
slate blue	1032	lime K.C.	2885
salt	1275	shale blue	2892
slate blue	1295	lime sft	2912
lime	1325	shale blue	2914
shale & shells	1490	lime shells&shale	2930
lime	1505	lime	2942
shale & shells	1520	shale blk	2945
red rock	1548	lime	2959
lime	1560	shale blue	2962
shale blue	1580	lime	2965
lime brkn	1685	lime,sft pay	2968
red rock	1690	lime& shale brks	2973
lime brkn	1780	Total Depth.	
lime	1800		
red rock	1807		
lime	1845	Ripped 7" w/csg	
shale red	1852	ripper from 2893 to	
lime	1877	98	
red rock-cave	1900	Acidized w/2000 Gals.	
lime	1970		
shale & shells	2010	sh gas 2060	
shale blue	2015	sh gas 2705	
lime	2030	sh oil 2730	
shale blue	2037	sh oil & gas 2892-98	
lime	2050		
shale blue	2055	5 BW 105-10	
lime	2065	HFW 280-320	
shale blue	2070	1 BW 1615-30	
shale & shells	2090	2 BW 1920-35	
shale blue	2115	$\frac{1}{2}$ BW 2740-60	
lime	2120		
shale blue	2168		