


55276

CENTRAL PETROLEUM CO., INC.
Zeman No. 1.

SEC. 16 T. 15 R. 12W
SWc NE

Total Depth. 3304'
Comm. 2-7-41 Comp. 3-28-41
Shot or Treated.
Contractor. Haynes & Anschutz
Issued. 5-17-41

County. Russell



CASING:

15 1/2" 380'P 8 1/4" 2390'P
12 " 585'P 65/8" 2962' UR 3134'P
10 " 2010'P 53/16" liner 195'@3290'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

cellar	10	lime brkn	2290	lime Arbuckle sft	3304
shale	165	shale & lime	2440	Total Depth.	
red rock	180	lime brkn	2465		
shale 10 BW	190	lime	2520		
sand	200	shale	2550	Hole filled 1000' sulphur	
shale	205	shale & shells	2575	wtr in 5 hrs.	
red rock	225	lime brkn	2595		
shale HFW	230	shale	2605	Oil shows :	
wtr sand	285	lime	2640	2647-50, 2985-89 1/2,	
shale	315	shale	2647	3050-54, 3065-70 1/2, and	
sand	320	lime	2668	3286	
shale 1 BW	395	shale	2670		
sand	400	lime 1/2 BW	2675	10 BW 190-200	
shale HFW	425	lime sdy	2680	HFW 230-75	
sand	440	lime	2740	1 BW 395-400	
sand & iron	445	shale	2743	HFW 425-40	
shale	480	lime	2760	1/2 BW 2675-80	
red rock	731	shale	2765	1/2 BW 3014-17	
lime	760	lime	2790	HFW 3107-17	
red rock	940	shale	2795		
shale	985	lime	2802	Anhydrite 731-60	
red rock	1025	shale	2805	Topeka 2605-40	
shale	1118	lime	2886	Dodge 2901-19	
salt	1357	shale blk	2890	Lansing 2965-3256	
shale	1360	lime	2893	Conglomerate 3256-80	
salt	1375	shale	2901	Arbuckle 3292-3304	
lime	1385	lime Dodge 1 1/2 BW	2919		
shale & shells	1400	red rock	2925		
lime	1405	shale	2930		
shale & lime	1525	shale & shells	2940		
red rock	1530	shale	2950		
lime	1535	lime	2977		
shale & shells	1550	shale	2980		
shale & lime	1635	lime sft & med	2990		
red rock	1660	lime hrd (1/2 BOPH 2985-90)	3007		
lime	1825	shale blue 1/2 BW	3011		
shale	1830	lime med to hrd	3026		
lime sdy	1855	shale blk	3029		
shale	1860	lime (1/2 BOPH 3065-70)	3100		
lime sharp	1870	lime - HFW	3117		
red rock	1885	shale	3122		
lime	1900	lime	3139		
red rock	1905	shale	3143		
lime	1920	lime	3160		
red rock	1925	shale	3165		
lime	1955	lime	3188		
shale	1965	shale	3195		
lime	1985	lime	3210		
red rock	2005	shale	3215		
lime 1/2 BW	2012	lime	3218		
lime	2045	shale	3225		
shale & shells	2055	lime	3242		
lime	2080	shale	3246		
shale	2085	lime	3256		
red rock	2090	conglomerate	3280		
lime	2110	lime	3286		
shale	2120	lime sdy	3288		
lime brkn	2140	lime hrd	3289		
lime	2165	lime sft	3290		
shale	2185	lime	3292		
shale & lime	2275	lime sdy	3295		